

LARP

BNL - FNAL - LBNL - SLAC

LARP BEAM INSTRUMENTATION


A. Ratti

LBNL

Presented at the DoE review of LARP

Fermilab

June 12 -14, 2006



LARP

Outline

Overview of existing instruments

Schottky Monitor (lead by FNAL)

Tune Feedback (lead by BNL)


Luminosity Monitor (lead by LBNL)

Common instrumentation issues

Data Acquisition

Documentation and integration at CERN

Budget and Schedule Status



LARP

Highlights

From Steve's highlights:


Simultaneous tune and coupling feedback was demonstrated in RHIC - a world first

US colliders are an essential part of the LARP contribution to the LHC

Developing all instruments with experimental support of colliding beam operations

Documentation, integration issues are becoming more urgent and being addressed with a systematic approach both within the LARP and the CERN (EDMS) frameworks

Year by year funding needs to be managed closely



LARP

Introduction

Three instruments at different levels of maturity

Schottky monitors will be mostly completed by the end of FY06


Luminosity monitors will be under production through 06 and into 07

Tune and coupling feedback are still under development and will reach a final design in early FY07

All three devices are on schedule to support LHC commissioning

The data acquisition platform is defined by CERN and therefore common to all LARP instruments

Successful workshop on April 25, 2006




LARP

Schottky Monitors

Advanced enabling technology for:

- Non invasive tune measurement for each ring
- Non invasive chromaticity measurements
- Measure momentum spread
- Continuous online emittance monitor
- Measure beam-beam tune shift

Build in capability to monitor gain variation with time
Measure individual or multiple bunches



LARP

Technical Approach

Center frequency of 4.8 GHz

3dB BW - 300 MHz

Sufficient for 25ns bunch spacing

Small longitudinal Z/n

No absorbers allowed

Below frequency of Schottky band overlap

Allows for adequate physical aperture

Matched pairs of SiO₂ Coax cables







Table 1. Parameters of LHC Schottky Pickup (unit: mm)


Slot length	Slot width	Slot Spacing	Number of Slots	Waveguide width	Waveguide height	Beam pipe width	Beam pipe height
20.52	2.032	2.032	246	47.549	22.149	60.00	60.00



LARP


Pickup and Adjacent Beampipe






LARP


Mode Launcher Impedance






LARP

Mode Launcher Response





LARP


Connections and Processing


Feedthroughs and tunnel connections
are critical

CERN ordering the coaxial cables

FNAL provided detailed layouts for
phase matched cables

Installation planned in point 4 of LHC







LARP


Tevatron Experience

Tevatron Single Bunch Horizontal Protons



60 Hz Modulation on Tevatron Schottky Signals







LARP

Schottky Measurements at Tevatron

Allows measurements of:

- Tunes from peak positions
- Momentum spread from average width
- Chromaticity from differential width
- Emittance from average band power






Schottky Electronics Block Diagram


LARP

Additional
downconversion
stage just added here



Notes: Red provided by CERN, Black by LARP
 1. Pickup will be designed by FNAL
 Fabricated by CERN. CERN will provide tank stand, motion controls, bake out hardware.
 2. Fermilab has developed software for measuring beam parameters. This software can be made available to CERN. Fermilab does not intend to port software to CERN control system.

Also shows roles and responsibilities
 Red = CERN, Black = FNAL




LARP

Schottky Processing Electronics

Triple down-conversion preserves single sideband signal with Chromaticity information

- First IF uses the 11th harmonic of the 400MHz clock to convert the 4.8 GHz signal to 400 MHz
- Second at 45 MHz, using a LO locked to the 40MHz LHC clock reference
A crystal filter selects a 15 kHz band of schottky signal
- Third IF takes the signal down to DC-80KHz baseband

Data is then collected with 20-24 bits CERN DAQ cards in DAB-IV environment



Schottky Monitor - Roles and Responsibilities

LARP

FNAL


- Deliver a complete, ready to print drawing package to CERN
- Deliver a full set of front end electronics to connect to the detectors
- Provide installation and hardware commissioning support

CERN

- Build beamline devices to FNAL's prints
- Provide local cabling, installation,
- Local Oscillators, Reference signals, Data Acquisition hardware
- Final integration with control system

LARP - Commissioning

- The beam commissioning of these devices will be supported by the Beam Commissioning group



LARP

Schottky Monitor Planning

FY06

Final Design Review at CERN on June 22

Lots of integration activities as well

CERN fabricates and installs the devices in the LHC

Summer 2006, depending upon LHC's installation schedule

All cables have been specified and requested


Including request for timing and synchronization signals

FNAL will build the analog processing electronics during the summer

FY07

Activities include hardware commissioning and installation support

In particular two trips to CERN, one to test the hardware without beam, and the next to test with beam (when beam occurs)



LARP

LUMI - Requirements

Requirements (Lumi mini Workshop, 16-17 Apr. 99)

- Absolute L measurement with $\delta L/L \sim 5\%$ for $L > 10^{30} \text{ cm}^{-2}\text{sec}^{-1}$
- Cross calibration with LHC experiment measurements of L (every few months)
- Sensitivity of L measurement to variations of IP position ($x^*, y^* < 1\text{mm}$) and crossing angle ($x^*, y^* < 10\mu\text{rad}$) less than 1%
- Dynamic range with "reasonable" acquisition times for 1% precision to cover $10^{28} \text{ cm}^{-2} \text{ sec}^{-1}$ to $10^{34} \text{ cm}^{-2} \text{ sec}^{-1}$
- Capable of use to keep machine tuned within $\sim 2\%$ of optimum L
- Bandwidth 40 MHz to resolve the luminosity of individual bunches
- Backgrounds less than 10% of the L signal and correctable

LBNL
25 Jan. 2002

40 MHz Ionization Chamber
W.C. Turner

11

Help bring beams into collisions too



LUMI - Specification

CERN
CH-1211 Geneva 23
Switzerland



the
Large
Hadron
Collider
project

LHC Project Document No.

LHC-B-ES-0007 rev 0.4

CERN Div./Group or Supplier/Contractor Document No.

AB-BDI

EDMS Document No.

347396

Date: 2003-06-11

Functional Specification

MEASUREMENT OF THE RELATIVE LUMINOSITY AT THE LHC

Abstract

This functional specification defines the requirements for the measurement and optimization of the interaction rates or relative luminosity at the four LHC interaction points. The beam and machine scenarios and the anticipated uses in operation are analysed to define the required dynamic ranges, precision, time response...of the machine luminometers. The potential for absolute calibration, the complementarities with the experimental absolute luminometers and the data exchange between machine and experiments are discussed and specified. The requirement for the measurement of the background to the experiments by standardized detectors was identified and will be dealt with in a separate document.

Prepared by

R. Assmann/AB-ABP
J.P. Koutchouk/AB-BDI
M. Placidi/AB-BDI
E. Tsesmelis/EST-LEA

Checked by :

Oliver Brüning [AB/ABP]
J-Jacques Gras [AB/BDI]
Rüdiger Schmidt [AB/CO]
Jörg Wenninger [AB/OP]

Approval Leader :

Approval Group Members

LTC: S. Myers, P. Collier; AB/ABP: J.-P. Riinaud, S. Fartoukh, W. Herr, F. Ruggiero;
AB/BDI: H. Schmickler, R. Jung, E. Bravin, W.C. Turner; AB/OP: S. Baird, K. Cornelis;
EST/LEA: K. Potter;
ALICE: D. Evans, C. Fabjan, L. Leistam, A. Morsch; ATLAS: N. Ellis, P. Grafstrom, M. Nessi;
CMS: A. Ball, A. Herve, M. Huhtinen, W. Smith; LHCb: R. Jacobsson, A. Smith, W. Witzeling;
TOTEM: M. Bozzo, K. Eggert, D. Macina, M. Oriunno;

Prepared by

R. Assmann/AB-ABP
J.P. Koutchouk/AB-BDI
M. Placidi/AB-BDI
E. Tsesmelis/EST-LEA

Checked by :

Oliver Brüning [AB/ABP]
J-Jacques Gras [AB/BDI]
Rüdiger Schmidt [AB/CO]
Jörg Wenninger [AB/OP]


Approval Leader :

Approval Group Members

LTC: S. Myers, P. Collier; AB/ABP: J.-P. Riinaud, S. Fartoukh, W. Herr, F. Ruggiero;
AB/BDI: H. Schmickler, R. Jung, E. Bravin, W.C. Turner; AB/OP: S. Baird, K. Cornelis;
EST/LEA: K. Potter;
ALICE: D. Evans, C. Fabjan, L. Leistam, A. Morsch; ATLAS: N. Ellis, P. Grafstrom, M. Nessi;
CMS: A. Ball, A. Herve, M. Huhtinen, W. Smith; LHCb: R. Jacobsson, A. Smith, W. Witzeling;
TOTEM: M. Bozzo, K. Eggert, D. Macina, M. Oriunno;



LUMI - Conceptual Design Argon Ionization Chamber




Signal is proportional to the number of parallel gaps
Capacitance add up with n. of gaps + slows down the signal

→ Optimized for 6 gaps

→ Must live in a radiation environment 100x worse than accelerator instruments have ever seen

→ ~10GGy/yr, ~10¹⁸ N/cm² over lifetime (20 yrs), ~10¹⁶ p/cm² over lifetime



LARP

LUMI Status

Final design complete

Successful design review on April 24, 2006

Most critical R&D parameters demonstrated


Successful high speed (40 MHz test) using X-ray beamline at ALS

Final design presented here

Some R&D still ongoing

Testing prototype in RHIC

Rad damage tests underway




LARP


Final Design Review Results

Excellent review

- Highlighted several areas of possible improvement
- Endorsed basic design
- Recognized progress
- Recommended fast path to production

Final report just released





LARP

Mechanical Design

Ready for final prints and production


Performed thermal and stress analysis

Performed gas flow modeling through the chamber

Completely revised the housing and fabrication





Detector nearly identical to the prototype

Fabrication process defined




LARP

Case is designed to manage stress levels



K. Chow


Max stress is <16kpsi (<110 MPa)




LARP

Gas flow through ionization chamber

Detail of ionization chamber without copper bar




With support plate displaced in beam direction




4 gas inlet holes on support plate

Chamber gas flow volume model



K. Chow


120 holes in ground plane, 1 mm diameter each




LAR^P

Gas velocity in production chamber

Velocity
(Contour 1)




[m s⁻¹]




This face is at a cut plane through center of front gas volume

K. Chow

Darkest blue areas are equivalent to less than 0.017 liter per hour flow









Compare: gas velocities in prototype chamber

LARP

Prototype ionization chamber
showing outline of 1/8 symmetric
gas flow model



Darkest blue areas are equivalent to less than 0.017 liter per hour flow



Thermal conditions during TAN bakeout

LARP

Bakeout operation

Heat up the beam tube to 200 deg C in 24 hours.

Stay at 200 deg C for a minimum of 24 hours


Ambient cooldown

Bakeout performed in situ whenever beam tube exposed to atmospheric pressure

Maximum temperature in absorber box is up to 300 deg C

FEA results

Temperatures after 20 hours




Details of the handling plan for LUMI are being formulated

K. Chow

Analysis will be used to estimate temperature rise in LUMI

Temperatures in LUMI should be monitored during bakeout (with thermocouples) to determine if it exceeds its allowable temperature


LUMI should be (partially) pulled out of slot if it may overheat (pullout has radiation exposure implications)




LARP

Signal Processing


- Very low noise pre-amp in the tunnel
- Shaper section completes the analog signal processing
- ADCs integrated in a VME64 mezzanine card
 - Interface defined by CERN BDI group






LARP

Electrical Connections





LARP



IBMS Mezzanine Board


Data from IBMS technical specifications document in EDMS (Jean-Jacques SAVIOZ)

IBMS Mezzanine Board contains:
Custom ASIC originally developed for the LHCb Preshower detector
14-bit digitizer (only 12 used).

ASIC:
Dual integrator + T/H circuit
One integrator operates while other is in reset mode.


Differential input.






LARP

Shaper Board and DAB64x boards





LARP

Testing at RHIC

RHIC run was suddenly restored

Presented plan at RHIC APAX meeting in November

Asked for 2 shifts of 3-4 hours each

Need dedicated collisions

Now setup in IR10, former PHOBOS area


While ideal running condition is Au-Au, this run is p-p

We'll focus on backgrounds and on establishing operation of the device - 250 GeV will help

Infinuim scope allows us to watch from LBL

Plan to use in parasitic mode while RHIC is running

Plan to replace with lumi DAQ system in the next run



Radiation Damage to passive components

LARP

Damage to passive components is mostly dominated by neutron scattering

DPA's are a best way to measure the effects of radiation exposure


While a DPA to first order is a DPA, neutron energy, flux, temperature changes can have a great impact on test results

If an atom is displaced and quickly recombines, it could be no problem

If this happens while an enormous amount of heat is dissipated, the material properties could easily change, the atom may not recombine...

Using the DPA approach, we can use neutrons at several test facilities

Still important to have relatively high energies



LARP

Rad Damage Testing

At CERN

At the ISOLDE ion source with a 1.4 GeV p beam from CERN PS Booster
~ 10^{13} protons per second

Testing two identical kits, one exposed ~3 months, the second ~ 9 months

At BNL

Thanks to our colleagues in the collimation group (T. Markievich, N. Simos), we were able to add our samples to tests they were planning at the RHIC linac (200 MeV)


Exposed all passive components to a dose ≥ 30 Grad

Going to > 100 Grad

Completed in June, in time for material's choice

After irradiation we will perform mechanical testing and metallurgical investigations of the samples.





Setting up a MARS model to calculate DPAs in this configuration and compare with LHC projections




LARP

Setup at ISOLDE's source

Our samples are mounted on the wall behind the source





LARP

Rad Damage of Active Components

In general a level of ~ 100 krad/yr is generally tolerated by bipolar transistors

Packaging front end electronics for fast replacement

Dual channel to overcome random failures


Recommend replacement after a given integrated dose

1-2 years at highest luminosity

Earlier operation at lower luminosity will allow for a longer time before replacement

Have a kit a BNL ready for testing with high energy p beams

Do we have a choice??



LARP

Integration planning at CERN

- Complete system description
 - Technical, installation, safety, electronics, responsibilities, deliverables...
- Met with all relevant parties at CERN
- Final draft at CERN
- EDMS process underway

LHC Project Document No.

LHC-

Page 3 of 13

Table of Contents

1. DISCLAIMER - INTRODUCTION	5
2. SYSTEM DESCRIPTION	5
2.1 INTRODUCTION	5
2.2 GAS SYSTEM.....	6
2.3 HIGH VOLTAGE AND DC SYSTEMS	6
2.4 REMOTE MONITORING AND EQUIPMENT PROTECTION	6
2.5 INSTALLATION.....	6
3. MODES OF OPERATION	7
4. OPERATING PARAMETERS	8
5. EXTERNAL CONNECTIONS	8
5.1 GAS LINES	8
5.2 SIGNAL, CONTROLS AND HV CABLES	8
5.3 NETWORK INTERFACES.....	8
6. SYSTEM SAFETY	8
6.1 RADIATION SAFETY	8
6.2 COMPRESSED GASES.....	9
6.3 HIGH VOLTAGE	9
7. GAS HANDLING SYSTEM	9
7.1 GAS DISTRIBUTION.....	9
7.2 TEMPERATURE AND PRESSURE MONITORING AND RELIEF	10
7.3 COMPRESSED GAS SAFETY CONSIDERATIONS	10
7.4 GAS ANALYSIS - SPECTROSCOPY + RADIATION.....	10
8. HIGH VOLTAGE DISTRIBUTION	10
8.1 DC BIAS TO THE ELECTRODES.....	10
8.2 CONTINUITY CHECK	10
9. DATA ACQUISITION SYSTEM	10
9.1 SYSTEM INFRASTRUCTURE - THE VME DABIV BOARD	10
9.2 MEZZANINE CARD	10
9.3 FPGA PROGRAMMING	11
10. CONTROL SYSTEM INTERFACE	11
11. HARDWARE COMMISSIONING	11
11.1 HV TESTING	11
11.2 SIGNAL TESTING PROCEDURE	11
11.3 HARDWARE CHECKOUT.....	12
12. PLANNING	12
12.1 MILESTONES	12
12.2 RESPONSIBILITIES	12
12.3 BEAM COMMISSIONING AND BEAM REQUIREMENTS	12
13. LUMINOSITY MEASUREMENTS IN IP2 AND IP8	12

CERN
CH-1211 Geneva 23
Switzerland




the
Large
Hadron
Collider
project

LHC Project Document No.
LHC-
CERN Project Document No.
EDMS Document No.

Date: 1999-09-22

Technical Specification	
LHC LUMINOSITY MONITOR	
<small>Abstract The LHC luminosity monitors are gas ionisation chambers that sample energy deposition in the forward TAN neural particle absorbers. These luminosity monitors are primarily sensitive to high energy neutrons produced near zero degrees by pp collisions at the IP. The neutron strikes in the TAN absorbers produce hadronic-electromagnetic showers that deposit energy by ionisation. The luminosity monitors are placed near the maximum of shower energy deposition in the TAN absorbers. Since the flux of neutrons and shower energy deposition are proportional to luminosity, the signal strength measured by the ionisation chambers provides a measurement of relative luminosity. The ionisation chambers and associated electronics have been designed to measure luminosity with 0.1% accuracy, or better, for the LHC. The ionisation chambers are segmented into quadrants to allow measurement of beam-beam crossing angle. Small fluctuations of the transverse position of one beam at the IP allow measurement of beam-beam separation at the IP. The measurement of beam-beam separation can then be used in a slow feedback loop to reduce the beam separation to zero and maintain the LHC in optimum luminosity.</small>	
<small>Prepared by:</small> [E.Bravin] [AB/BDI] [eric.bravin@cern.ch] [A.Ratti] [LHC] [bratti@lbl.gov]	<small>Checked by:</small>



LARP

Integration effort at CERN

~8 FTE-months spent at CERN in integration activities

Two integration meetings in January and March

Including an integration workshop with all groups instrumenting TAN


Opening a team account to support local expenses

Planning more visits to further plans and follow through

TS/LEA group now responsible to coordinate installation and documentation of TAN instrumentation area

Generates 3D layout of the area

Coordinates gas installation activities



LARP

LUMI Long Term Plans (from 2005)

FY06

Fabrication of first article

Design of auxiliary hardware

Device tests, electronics integration and performance qualification

Deliver first unit to CERN - **delayed ~3 months**

FY07

Fabricate balance of units and auxiliary hardware


Transfer to CERN

Installation support

Commissioning support

FY08

Post-commissioning and pre-operations support




LARP

Tune Feedback

- Objective: Control Tune, Coupling and eventually chromaticity during ramp and store
- Recent Progress
 - Tune and Coupling feedback used in RHIC run 6, a world first
 - Major Improvements for RHIC Run 6
 - coupling feedback
 - Direct Diode Detection (3D) analog front end
 - Delayed Milestones
 - Final Design Review – Oct. 26, 2006
 - SPS testing – planned for this summer, after RHIC run

3D system is an excellent tool for Beam Transfer Function Measurements






LARP

VME BBQ in RHIC - 2 improvements



Continuous coupling measurement –
made coupling feedback possible, which made tune feedback possible

Direct Diode Detection Analog Front End
(3D AFE) – improved sensitivity
(~10nm!) and dynamic range






Coupling Measurement with PLL Tune Tracker





Tracking the vertical mode in the horizontal plane & vice-versa allows the coupling parameters to be calculated

C-A/AP/204 - Towards a Robust Phase Locked Loop Tune Feedback System, R. Jones et al
http://www.rhichome.bnl.gov/AP/ap_notes/cad_ap_index.html



RHIC VME-based System Diagram







LARP



Mains Harmonics



- Direct excitation of betatron line by high harmonics of power line frequency
- Recent measurements show it ~80dB above 3D noise floor
- Studies identified it as main dipoles
 - correlation with coupling
 - correlation with ramping (next slide)
- Seen at all accelerators where 3D AFE has been installed
- ~50dB stronger at RHIC than elsewhere




- Complicates transition to operational status in RHIC
- Scheduled for 3 hours dedicated beam time during June 15th beam studies







mains harmonics 'noise' breaks the PLL phase lock



LARP

Chromaticity Feedback

Challenge:


- persistent current effects in SC magnets can strongly perturb machine lattice, especially during energy ramp (aka “snapback”)
 - Betatron tunes ($Q_{x,y}$) and chromaticities ($Q'_{x,y} = EdQ_{x,y}/dE$) can vary significantly due to “snapback” resulting in beam loss, emittance growth.
- Effects for LHC predicted to be large.

Solution: make fast, precision Q , Q' measurements and use these signals to feedback to tuning quadrupoles and sextupoles.


This effort is ideally suited for a collaboration with RHIC, which can be the benchmark and testing ground for this effort.

- slow (1Hz) radial (1mm) modulation – next slide
- faster phase modulation – under investigation


chrom - good results under sequencer control




dp/p of $\pm 10^{-4}$ gives $\sim \pm 100\mu$ radial modulation (RHIC&LHC)



in RHIC modulation is at 1Hz





LARP

Scope, Boundaries, Responsibilities...

CERN provides all hardware for LHC

- kicker amplifiers, kickers, and pickups
- Direct Diode Detection AFEs
- Digitizer boards
- DAB64 Boards
- VME crates and crate computers
- non-PLL gate array code

LARP provides software

- PLL-specific gate array code
- LabVIEW control program
- testing at RHIC, with and without beam
- commissioning support at LHC

CERN
CH-1211 Geneva 23
Switzerland



the
Large
Hadron
Collider
project

LHC Project Document No.

LHC-BQ-ES-0001 draft

CERN Div./Group or Supplier/Contractor Document No.

AB/BDI

EDMS Document No.

Date: 2005-06-14

Functional Specification

DEFINITION OF THE SCOPE, BOUNDARIES AND SHARE OF RESPONSIBILITIES FOR THE LHC TUNE FEEDBACK TASK WITHIN THE US-LARP FRAMEWORK

Abstract

This specification will define the scope of the LHC tune feedback task within the US LHC Accelerator Research Programme (LARP). The boundaries and share of responsibilities between CERN and its US partners will be clearly defined.

Prepared by :


Rhodri Jones
[AB-BDI/CERN]
rhodri.jones@CERN.CH
Peter Cameron
[BNL]
cameron@BNL.GOV


Checked by :

Approval Leader:



LARP Responsibilities







LARP

FY06 Milestones and Deliverables

- January: VME-based Baseband Tune (BBQ) in RHIC
 - deal with coupling problem – coupling breaks tune feedback
 - world first simultaneous tune and coupling feedback – delivered decoupled beam to full energy on the first attempt
 - Improvement of mains harmonics is needed to continue developing chrom. feedback,...
 - dedicated study – 3 hours dedicated beam time on June 15th
- May: Final Design Review – moved to October
 - Still allows for on time delivery for LHC commissioning
- June : DAB-based BBQ for SPS testing
 - Triumf DAB board delays
 - Moved to September






LARP


FY07 Milestones and Deliverables

- September + October – Operation of DAB-based BBQ at SPS
- October 26 – Final Design Review
- November onwards – further evaluation of VME-based Baseband Tune (BBQ) in RHIC
 - Mains harmonics
 - Loop parameters
 - Chromaticity feedback,...
- January – commissioning of DAB-based BBQ
- February to end of RHIC Run 7 – evaluation of DAB-based BBQ in RHIC
- July – finalization of LHC system
- August onwards – support of installation and commissioning at LHC




LARP

LHC DAQ Interface - DABIV Board



D Bishop, TRIUMF



LARP

LARP DAQ Workshop

Attended by representatives of all labs


April 25, 2006

Daryl Bishop (TRUIMF), designer of the DAB board, gave a comprehensive description of the board design and its firmware programming

Rhodri Jones did a live demonstration of the hardware functionality at LBL

Used signal from pulse generator, processed by LUMI analog shaper

Round table discussion on how to implement system at LARP labs



DAQ software/firmware for LARP instruments

LARP

Real Time OS problem to compile LynxOS at US labs

- This stalled our efforts for months

- Licensing problem

LabView proposed by CERN

- Use VME-USB bridge card

LARP labs can develop expert Vis in LabView and deliver to CERN

- Uses the bridge card in the US


CERN implements the FESA interface, provides LabView connection

Expert panels available through CERN's FESA

LARP labs provide functional specification of memory interface

CERN develops GUIs for device controls

- Both expert and operator



Open Issue/Opportunity

LARP

LHC@FNAL opens the door to experiments or observations at LHC directly from LARP sites

FNAL is leading the way

Ideal for 'passive' devices


I.e. Schottky monitor, luminosity monitor

Could make present effort on Schottky more effective

Not clear how much will be available by commissioning

CERN controls must be deeply involved for this to happen

CERN is now looking at ways to facilitate




LARP Instrumentation Integration Plan

LARP

Planned documentation for each instrument

1. FS - Roles and Responsibilities
Defines who does what, when
2. ES- Technical Specification
Complete description of the device, its interfaces, its requirements....
3. ES - Functional Spec (of DAB 64x interface)
Definition of what functions and features are included in the data acquisition system
4. ES - Memory Map of Firmware
How the data is transferred to the control system
5. Any other document
(ES) Safety, installation, HW checkout and commissioning,
6. FS - Acceptance Plan and signoff list
Contains a list of deliverables from LARP to CERN
Signoff list
Once accepted, defines the end point of LARP's contribution to the instrument

FS= Functional Specification ES=Engineering Specification




LARP

Implementation

The above docs have approvals on both sides
CERN and LARP

PIs are the single points of contact at each side of the ocean
Documents reside in EDMS and in LARP's databases

We are working towards the completion of the first two and the last one
in June



LARP


Response to Previous Reviews

- Task sheets are revised as plans change:
 1. When the RHIC run was revived, the plan for tune feedback changed completely, an updated task sheet reflects the changes
 2. Annual system specific LARP reviews validate the work, its technical merit, funding requests and proposed schedules. Both are management tools to ensure tracking of progress and convergence towards the program's goals

- CERN decided to adopt a different technology for monitoring luminosity in IP2 and 8, and is no longer seeking ionization chambers for these IPs

- Only minimal funding goes to ZDC electronics, to ensure that we will have analog signals available to cross calibrate the devices and monitor performance in particular at low luminosity

Covered and integrated in Steve's scorecard



LARP

New Tasks

Several new tasks are emerging

AC Dipole


Synchrotron light based diagnostics

Being considered with other AS new proposals

As the existing tasks come to an end, funds will become available for new proposals

Instruments are chosen in close collaboration with CERN

Current devices were not part of baseline design of LHC




LARP

Spending to date

	Budget	Spent	Balance (as of 5.31.2006)
Luminosity Monitor	960	485	475
Schottky Monitor	245	151	94
Tune Feedback	430	349	81

in \$1,000s



LARP

Conclusions - Challenges

Funding

We are working with LARP management to continue securing adequate funding


With LHC commissioning approaching, we cannot tolerate schedule slips

LARP task sheets continue to define scope and budget year by year

Funding requests are also managed through task sheets

Detail 'project' reviews validate overall cost and schedule

Integration with beam commissioning activities is essential to the survival of the instruments provided by the LARP collaboration and LARP is planning accordingly



LARP

Summary

LARP Instrumentation will build, commission, and integrate into LHC operations advanced instrumentation and diagnostics for helping LHC

- reach design energy

- reach design luminosity

Strong collaborative efforts are in place and evolving

- Tune feedback is fully leveraging RHIC experience and includes CERN staff

- Lumi testing in RHIC is extremely valuable

- Schottky's experience at FNAL is a great asset

- US colliders are an essential test bed for system development

This program will advance the US HEP program by

- Enhancing US accelerator skills

- Developing advanced diagnostic techniques that will apply to present and future US programs

- Help maximize LHC performance