


***LARP***

***BNL - FNAL - LBNL - SLAC***

## **LARP BEAM INSTRUMENTATION**

A. Ratti, LBNL  
and many others

Fermilab  
October 27-28, 2008



**LARP**

# Outline

Progress update of existing instruments

- Schottky Monitor (lead by FNAL)

- Chromaticity Feedback (lead by BNL --> FNAL)

- Luminosity Monitor (lead by LBNL)

- AC Dipole (lead by UT --> BNL)


Most of these transition to Beam Commissioning in FY09

- Not all lumi monitors are now installed but plan to have all system installed well in advance of 2009 run

New tasks

- LHC RF Controls Modeling (lead by SLAC)

Integration at CERN



**LARP**

# Introduction

First Four instruments are approaching completion at different stages

- Schottky monitors are delivered, installed and bench tested

- Luminosity monitors are in final production

  - will be ready for LHC's 2009 run

- Tune and coupling feedback is evolving to chromaticity feedback

- LHC AC Dipole is mostly in the hands of CERN,


  - US scientists ready to participate and continue to develop "local" systems

Three tasks successfully completed in FY08

- Maintain a minimum level of funding to support LHC beam commissioning

One new task added for FY09

- LLRF modeling for the LHC



**LARP**

## Schottky Monitors Status

Project complete

Documentation delivered


One trip taken in June to complete hardware commissioning

Waiting for beam

Early circulating team likely have gave signals

CERN staff if monitoring the devices

LAFS integrating software interfaces



**LARP**

## Schottky Hardware Commissioning at CERN

Tested:


The hardware control interface and cabling.

all switches, amps, attenuators in situ.

The scope was installed, but it did not have a working interface at the time.

CERN combined the Labview software from Fermilab for controlling amps, switches, attenuators with Labview software written at CERN to control the DAB board and FFT.

As a final test of the system, we demonstrated remote control of most of the hardware from the meeting room (except MUX and front end phase shifter and attenuator).



**LARP**

## Schottky Next Steps

Complete hardware for automation of measurements

- Part of CERN's original responsibility


- Motor control drivers for the front end phase shifter and variable attenuator.

- Signal multiplexer for timing channels to the oscilloscope.

Develop automation software

- LAFS could help

LARP (FNAL) ready to take beam commissioning trip(s) in support of device operations



**LARP**

# Chromaticity Tracking - History

Objective: Develop chromaticity tracking during ramp and store

## Tune and Coupling Feedback

Simultaneous Tune and Coupling feedback used in RHIC run 6


RHIC run 7 and 8 - Tune and Coupling feedback operational

Task ended in FY07

P. Cameron now working at NSLS-II

Available to participate in short term visits

CY Tan (FNAL) now leads the activity



# Chromaticity Tracking and Feedback

**LARP**

## Challenge:


- persistent current effects in SC magnets can strongly perturb machine lattice, especially during energy ramp (aka “snapback”)
  - Betatron tunes ( $Q_{x,y}$ ) and chromaticities ( $Q'_{x,y} = EdQ_{x,y}/dE$ ) can vary significantly due to “snapback” resulting in beam loss, emittance growth.
- Effects for LHC predicted to be large.

**Solution:** make fast, precision  $Q$ ,  $Q'$  measurements and use these signals to feedback to tuning quadrupoles and sextupoles.

This effort is ideally suited for a collaboration with RHIC, which can be the benchmark and testing ground for this effort.

- slow (1Hz) radial (1mm) modulation
- faster phase modulation





**LARP**

## Plans for FY09

### 1. Continuous head-tail

Machine studies at the SPS during the first week of November where head-tail data will be collected

Participate remotely using LHC@FNAL and will analyse the data.


### 2. Phase modulation method

The method has been recently made operational in the Tevatron.

A write up of the technique will be made to the collaborators very soon.

### 3. Travel to CERN

- tune tracker, chromaticity tracker commissioning
- machine studies for continuous head-tail.



**LARP**

## AC Dipole

Started in FY07 under by S. Kopp (UT, Austin)


FNAL graduate student -- now Toohig fellow  
with support from FNAL scientists

VERY active involvement from BNL, FNAL and CERN

All three labs have AC dipole activities

All labs contributing resources to make it happen

LARP committed to develop concepts on US colliders and provide  
system description for CERN to implement in LHC



**LARP**

## Status of AC dipole

All collider labs actively involved

- FNAL implemented a system (aka musical dipoles)
  - Tested non linear optics at Tevatrons injection
  - Part of Ryoichi's PhD work
- BNL developing a high Q power system as a supply for these applications
- CERN has own group and has built a system
  - Benefit from LARP's experience

Mei Bai new task leader

Ryoichi now a Toohig fellow at BNL

FY09:



- Plan to perform design studies at BNL for validation of measurement methods in preparation of LHC commissioning
- Participate in LHC commissioning

## AC Dipole Task, FY08 Activity

### • Tev. Nonlinear Dynamics Study (FNAL)



Spectrum of TBT data tells distribution of nonlinear driving terms in a ring.




LARP CM11 - Oct Q8

Beam Instrumentation-

(Details in PhD thesis of R. Miyamoto)


### • AC Dipole Tuning Scheme (BNL)


Capacitor bank allows  $\pm 15\%$  (0.255 - 0.345 in tune, 2.867-3.880kHz) of tuning rang.



### • Further Development of Tuning Scheme (BNL)

A dynamic tuning technique using single switched capacitor (simulation).





**LARP**

## AC Dipole Task, Plan in FY09

### Focusing on Commissioning

LHC AC dipole system to achieve the design goal of delivering 1800 Amps @ 3kHz  
Control software

### Development of Measurement Technique/Application


Linear optics measurement

A lot of data have been taken in RHIC and Tevatron

Help the development of LHC on-line optics measurement/gradient error correction application such as SVD and MIA

Dynamic aperture measurement

Non-linear resonance driving term measurement




***LARP***

## New Task - LHC LLRF Modeling

Lead by SLAC (J. Fox)

Apply extensive modeling experience developed and tested in PEP-II to  
understand the LHC RF controls  
identify optimal operating point  
determine weaknesses and derive solutions

J. Fox and others from SLAC already involved in hardware  
commissioning and testing in 2008




**LARP**

## LHC LLRF Modeling

Scope of work:

- PEP-II and LHC LLRF systems are very similar
- LHC work fits into two related activities:
  - RF Station/Beam Dynamics Interaction Model
  - LLRF Commissioning and optimal configuration tools
    - Allows estimation of open-loop stability margins from closed-loop data. Model based station configuration allows station and beam dynamics to be optimally configured in operating stations with beam.



## LHC LLRF Plans FY 2009

### *LARP*

Expand configuration tools for CERN use, including full LLRF controller  
(Direct and 1-Turn Feedback loops)

Participate in commissioning measurements

Validation of simulation

In depth beam/model verification

Study of imperfections, technology limits


Estimation of noise floors and impact on machine performance

Estimation of system limits

Longitudinal emittance analysis

Use simulation and commissioning experience to improve LLRF implementation.





**LARP**

## Luminosity Monitor

### Two separate activities:

1. Fabrication project --> deliver 4 detectors and all auxiliary equipment  
Install well in advance of 2009 run  
Well in advance = end of February 2009  
Task to end in FY09
2. Physics studies and beam commissioning  
Work will carry on into LHC operations



10-Sep-08  
15:44:50

**1**  
2 ps  
20.0 mV  
0.2 mV

**2**  
2 ps  
20.0 mV  
12.6 mV

**3**  
2 ps  
20.0 mV  
8.7 mV

**4**  
2 ps  
20.0 mV  
-1.5 mV

Δt 1.025 ps  $V_{pp}$  975.2 mV 100 ns/div

**1** DC 8.6 mV

**TRIGGER SETUP**

Trigger on **1** 2 3 4 Ext Line


Coupling **1** AC LF HZ J HF RE I MF

Slope **1** Pos Neg Window

Holdoff **OFF** Time Ext

**NOISE**


LARP CM11 - Oct 08



*LARP*

## Accomplishments in FY08

- Recorded first beam on day one
- Delivered four detectors to CERN
- Completed (simplified) gas systems
- Completed phase 1 firmware and software programming
- Systems integration underway



**LARP**

## FY08 Highlights

### HV cables performance

- Initial design had unexpected leaks

- Caused noise comparable to actual lumi signals

- Resulted in the complete redesign of the flange/HV cable assembly

### Recovered from HV cable leaks

- Now working on integration of PA and Detector

### As we were developing a solution for HV cables, we completed the detectors


- Two shipped and installed in LHC in Spring

- Adequate for low luminosity run in 2008

- Must be retrofit to match final design

- Balance (2 more) at CERN ready for installation

- New configuration completed in September



**LARP**

## HV Cable Problems


Original design implemented commercial rad-hard ( $\text{SiO}_2$ ) cables  
very long lead items (6-9 months)

When connected to very sensitive charge pre-amplifiers a small number of charges migrating across the gap results in pulses like those from the detector

In many cases high rates ( $> 100$  Hz)  
not acceptable

Unexpected, passed all project reviews

Resulted in the decision to design cables ad-hoc



**LARP**


## New Cable Design

Strong boundary conditions:

- sustain GRad-doses of radiation
- 50 Ohms configuration
- no HV leaks
- no long lead items, or custom designed parts
- no gas volume to act as detector
- fit in existing space to prevent re-design/manufacturing of existing detector parts

Engineered a solution using COTS

- 5 kV commercial feed-throughs
- glass and ceramic insulators
- standard copper tubes




**LARP**

## GAS Systems

Reduced scope to conserve money  
No active pressure/flow control  
Simple readout system




Delivered to CERN in June  
Installed by CERN both at pt1 and pt5






**LARP**

## Detector Assembly with new cables









**LARP**

## Detector Assembly







***LARP***

## Detector Assembly - 1

1. Install inner conductors, glass and ceramic insulators
2. Safety wiring holds ceramic stops






**LARP**

## Detector Assembly - 2

3. Mount copper support block to flange  
Gas feedline connected
4. Mount sensor assembly on copper support block






## Detector Assembly - 3


**LARP**

5. Custom made connections to each quadrant



Adjusted for HV  
performance






## Detector Assembly - 4



Install on housing  
TiN seal






LADD

## Pre-Amplifier Assembly





**LARP**

## Pre-Amplifier Production

### PA Assembly process

- PA board loaded by vendor

- Load HV board

- Mate HV board to PA board

- Fab and mount shield board

- Connect HV relays board and compartment

- Wire 28 pin Burndy connector


  - 4x2 DC bias supplies, 3x3 RTD signals, 4+2 Relay selector bias,  
5 BJT damage

All parts at LBL (need shield boards)

Several cleaning steps and slow soldering of ground shields to maintain HV performance


6-8 days per unit






**LARP**

# Electronics - Shapers







**LARP**

## Shapers - Plans

Package in separate chassis

- Control noise and interference


- Does not require VME installation

- Needs independent power supply

Bench test and integrate with Pre-Amps


Need 2 per IP, 4 total


- Will assemble one spare




**LARP**


## DAQ System Layout






## DAQ programming







**LARP**

## Test during SPS beam test


### First test in the SPS

Good agreement with NIM scalers


Some adjustment required

Learned we need an even/odd gain  
and offset adjustment

IBMS boards have two digitizers  
each









**LARP**

## Detector-PA Integration


Detector - Pre-Amp studies

Understand interdependencies

Optimize configuration



Test pulse - with and without load (detector)



**LARP**

# Pre-Amp Shaper Integration


## Pre-Amp Shaper studies


Optimize => minimize peaking time

Package shaper in shielded box

Study interaction with PA

Study/measure effect of long cable





## Detector Testing @ ALS

*LARP*

Since LHC beam returns in 2009 we plan to test the (spare) detector @ ALS BTS line in November-December

Validate new cable configuration on ALS beam

Test cable performance with high intensity signals


Infrastructure available from previous test

2 axis table, gas lines, signal lines

Important to coordinate with analog electronics integration

Only one spare available





## Installation and Commissioning

### *LARP*

Installation planned in collaboration with LHCf, Atlas and CMS ZDCs  
thanks to CERN's TS/LEA group

Extensive effort at CERN in integration activities

- Have office + lab at CERN

- A team account to support local expenses


CERN (Enrico's group) increasingly involved

LHC commissioning team starting to get involved

- Optimization of collisions

SLAC LTV (A. Fisher) available to participate to beam commissioning at CERN





**LARP**

## Handoff to CERN

CERN has been involved with many aspects of systems

- Increased presence since 2007

- Contributions to detector rework and optimization

- Gas systems installation and commissioning

Inviting CERN to participate to Berkeley activities (visit in Nov.-Dec.)

- Beam test at ALS --> detector operation


- Bench test of DAQ phase I firmware

- Analog electronics modules production and testing

- pre-amp and shaper

Plan to continue during installation and HW commissioning at CERN

Continue CERN's involvement in firmware development during phase II programming



*LARP*

# Luminosity Monitor Commissioning Plans

Commissioning will continue with each change in LHC operating conditions


Since LHC won't reach nominal luminosity, must continue commissioning BRAN in FY10

Plan dependent on luminosity and fill pattern

Need simulations at each LHC energy

Need presence of personnel at CERN

Will take effort to make BRAN part of LHC beam instrumentation




**LARP**

## Stages to Maximum LHC Luminosity CERN EDMS 347396

Mode	Bunches	Bunch Spacing	Luminosity [ $\text{cm}^{-2} \text{s}^{-1}$ ]	Interactions/Xsing	Mean pulse height/occupied bunch Xsing - mV
A-Collision studies with single pilot bunch beam - no crossing angle	1	N/A	$2.5 \cdot 10^{26}$ - $3.7 \cdot 10^{27}$	0.0006-0.092	0.04-0.53
B-Collision studies with single higher intensity bunch - no crossing angle	1	N/A	$1.1 \cdot 10^{29}$ - $4.3 \cdot 10^{30}$	0.27-10.71	16-611
C-Early p-p luminosity	43	2.025 $\mu\text{s}$	$4.8 \cdot 10^{30}$ - $8.4 \cdot 10^{31}$	0.28-4.86	15-277
	2808	25 ns	$6.5 \cdot 10^{32}$	0.58	33
	936	75 ns	$1.8 \cdot 10^{33}$	4.79	273
D-Nominal p-p luminosity	2808	25 ns	$1.0 \cdot 10^{34}$	8.87	506
E-Ultimate p-p luminosity	2808	25 ns	$2.3 \cdot 10^{34}$	20.39	1163

Pressure = 8 atm - (57 mV for each 7 TeV collision)



# BRAN Instrument Commissioning Plan

## **LARP**

### **A—Collision studies with single pilot bunch beam - no crossing angle**

Collision rate too low to use as a luminosity monitor

Minimize noise

Get baseline software and hardware ready

Study beam background (beam-gas, neutron ...)

### **B—Collision studies with single higher intensity bunch - no crossing angle**

Start in pulse counting mode

Transition to pulse height mode

Plan for crossing angle algorithms

Need sustained presence at CERN

### **C—Early p-p luminosity**

Develop deconvolution algorithms

May need deconvolution for this phase

Study crossing angle algorithms

Still in counting mode for most of this period

Develop pulse height mode algorithms

### **D—Nominal p-p luminosity**


Pulse height mode

Deconvolution

Detector needs to fully commissioned with gas flow

### **E—Ultimate p-p luminosity**

Might need to lower pressure to reduce signal strength



***LARP***

## Mode A + B-Circulating Beam

Measure noise rates and compare to expected

Measure interactions

- beam halo with beam pipe

- beam gas

- collimator


Synchronize DAQ

Measure for occupied and unoccupied bunches

- pulse height

- pulse shape


Compare to simulations



**LARP**

## Mode C – Collisions

- Synchronize DAQ and LHC clock
- Measure counting rates as a function of measured voltage
- Determine threshold for pulse counting
- Verify bunch pattern
- Compare luminosity measurement with other detectors
- Analyze beam background
- Develop and test deconvolution algorithms
- Compare to simulations



**LARP**

## Mode D – Nominal luminosity

Transition to pulse height counting mode

Compare to counting mode


Cross correlate with other luminosity detectors

Compare with simulation and expected fill pattern

Study crossing angle calculation

Test and calibrate with LHC beam





***LARP***


## Lumi FY09 Beam Commissioning Plans

Commission detector with beam

Cross correlate with PMT luminosity system

Integrate DAQ into LHC control system

Compare with models



**LARP**

## Summary

LARP Instrumentation has delivered and will commission into LHC operations  
advanced instrumentation and diagnostics for helping the machine

- reach design energy

- reach design luminosity

Strong collaborative efforts are in place and evolving

- Tune feedback is fully leveraging RHIC experience and includes CERN staff

- Lumi testing in RHIC is extremely valuable, CERN involvement increasing

- Schottky's experience at FNAL is a great asset

- US colliders are an essential test bed for system development

This program will advance the US HEP program by

- Enhancing US accelerator skills

- Developing advanced diagnostic techniques that will apply to present and future US programs

- Help maximize LHC performance