

# LHC Integration of a Crab Cavity (Summary & Update of a talk at BNL WS)

**J. Tückmantel**

**CERN-AB-RF**



**Legend:**

♥ : could / should (compatibility) be obtained/made by CERN,  
(but no promises of delivery today)

✱ : in radiation shielded area

The Mont Blanc as seen from Meyrin  
400 mm lens, © J.T.



## Survey (single, temporary CC) : best location at IP4 (ex-ALEPH)

- beam line centers are separated by 42 cm: enough lateral space
- the space foreseen for the 200 MHz capture cavities (+) is still free  
(but might get needed for increasing beam current, at least 1 year forewarning)
- the space reserved for the transverse damper reserve is still free  
(but might get needed for increasing beam current, forewarning: fabrication time)
- the 400 MHz main RF is at IP4: RF infra-structure exists  
(RF reference, cooling water, ...) (but no guarantee for simple hook-up)
- foreseen location for the transmitters for the capture cavities is less than 100m away from CC (RF loop gain  $\geq 100$ ) → place CC transmitter there (**radiation protected area**)

(+) staged



- Cryogenic liquids exist at IP4 with  $T \leq 1.9\text{K}$  and  $4.5\text{K}$

**BUT**

- pressure rises to 20 bar when magnet quench -> safety system (♥ as for main RF)
- the  $1.9\text{K}$  LHe is repressurized at 1 bar, not boiling -> not directly usable for sc. cavities
- LHe operational  $T$  (2 or  $4.5\text{K}$ ) still open
  - if  $4.5\text{ K}$ : ‘steal’ at main RF / equivalent system apart (♥)
  - if  $2\text{ K}$ : (small) cold compressor for CC/ tapping ??
- cryo supply to be settled with AT-CR (cut metal !) (♥ ♥ ♥)

**most complex part of the set-up**



## Additional installations in the tunnel & LEP's klystron gallery

- 800 MHz transmitter at a few 10 kW (\*, ♥)
  - RF group needs (for SPS) exactly such amplifiers → use spare
- HV supply (\*, ♥) for transmitter (a few 10 kV for IOT or klystron)
  - main transformer on ground level / hook onto main RF supply ?
- cooling water for transmitter: main RF klystrons 'next door' ... (♥)
- cooling water (♥) HOM dump cooling (if KEK/Cornell HOM design)
- compressed air (♥) (open/close [RF shielded] beam valves (♥))
- 240 / 3x400 V supply (♥) for removable vacuum pumps (♥),....
- High voltage cable (♥) for ion sputter pump (♥), HV supply (\*, ♥)
- connection (♥) to data bus (controls net-work (\*)) and cryo-controls
- control electronic crates (\*, {♥})

(\*) in radiation shielded area



## Requirements for cryo-module:

- stable support (with wheels ?) and solid anchor-points (shaft !)
- Exterior dimensions - including non-detachable parts (coupler(s), ..)
  - fit LHC transport zone: 'roll' CC module to its place
  - once CC placed: leave room for other LHC components to pass
- remote controlled transverse positioning of cavity and/or cryostat
- valve/JT<sup>1</sup> cold box on module ? (to be discussed with AT-CR)
- He rupture disk (♥) & self-closing (small) tap (♥)
- matching taps (♥) for cryogenic liquid/gas, 'warm' return gas
- LHe level gauge (♥), He pressure gauge (♥)
- dedicated T-sensors (♥) for cool-down, survey when 'warm idling'

<sup>1</sup> Joule-Thomson





**Thank you  
for your  
attention!**