

Lumi Plans to Complete

Alex and Sergio



Introduction

- We will be presenting each task to complete the project following the WBS prepared
- Additional and separate tasks are shown for beam commissioning support

-
- 1 Lumi Project
 - 1.1 Systems Production
 - 1.1.1 Electronics
 - 1.1.2 Gas Systems Upgrades
 - 1.1.3 Detector Upgrades
 - 1.1.4 DAQ System
 - 1.1.5 Documentation
 - 1.2 Hardware Commissioning at CERN
 - 1.3 DAQ Integration with CERN Software
 - 1.4 Physics Studies
 - 1.5 Project Oversight
 - 2 Lumi Beam Commissioning





Analog Electronics

- Pre-Amps Production
 - Shield board
 - Signal board
 - HV board
 - Relay board

Detector-PA Integration

- Detector - PreAmp studies
 - Understand interdependencies
 - Optimize configuration




Test pulse - with and without load (detector)



PA Production - HV board

- PA board loaded by vendor
- Load HV Board
 - Parts stress relieved
 - Two cleaning phases
- Mate HV board to PA board
 - HV cables added and terminated to the board
 - Need more cleaning of HV board
 - Minimize heat on HV cables as it deteriorates performance

PA HV Board





PA Production - Shield board

- The shield board is mounted in between the two PA/HV assemblies
- Just a ground plane
 - Carries one RTD and two BJT to monitor radiation damage
- This provides the assembly of the interior of the PA housing
- Coax output cables are added to both PA boards

PA-HV boards





PA Production - HV Relays

- HV relays are in a single board
 - Switch each channel between either side of the PA boards
 - Individually controlled
- Board is mounted in “input” compartment and separates it from PA/HV assemblies
 - Minimize noise and crosstalk

PA HV Compartment






PA Production - Wiring

- Once all boards are assembled, we can run the RTD wires
 - Pass signal from detector to 28 pin connector
- Run all wires to 28 pin connector
 - 4x2 DC bias supplies, 3x3 RTD signals, 4+2 Relay selector bias, 5 BJT damage

PA Wired to Burndy






Pre-Amp Shaper Integration Studies

- Pre-Amp Shaper studies
 - Optimize => minimize peaking time
 - Package shaper in shielded box
 - Study interaction with PA
 - Study/measure effect of long cable

Electronics - Shapers





Shapers - Plans

- Package in separate chassis
 - Control noise and interference
 - Does not require VME installation
 - Needs independent power supply
- Bench test and integrate with Pre-Amps
- Need 2 per IP, 4 total
 - Will assemble one spare



Electronics - Racks

- Detector Interface Chassis
- Cabling
 - by CERN
- Equipment (procurement)
 - Scopes
 - Linear Power Supplies (from CERN)
 - 1 15V 1.5A Supplies
 - SCEM code: 07.61.24.150.7; CNB: CN5-151.5-CERN-V-CAP
 - 4 $\pm 15V$ Supplies
 - SCEM code: 07.61.24.160.5; CNB: CN5-D151-CERN-V-CAP
 - 1 5V 2.5A Supply
 - SCEM code: 07.61.24.130.1; CNB: CN5-52.5-CERN-V-CAP
 - Shaper Power supplies - 6V, 0.5A



Detector Interface Chassis

Functions:

- Power 2 Preamps
- Read Preamp/Detector RTDs
 - through Omega DACScan
- Control Preamp Relays
 - through Omega DACScan and front panel
- Measure Preamp Supply voltages and currents
 - through Omega DACScan
- Front panel Test Points for Preamp supply voltages and currents
- Power selector switches in the preamps




Detector Interface Chassis - 2

- Interfaces
 - 2 Preamps
 - 14 twisted pairs - 28 pin Burndy
 - Power from CERN power supplies
 - Omega DACScan
 - Front Panel
 - Meters, lights, switches

Detector Interface - Analog


Signal Conditioners:

- OM5-IP-100-C
 - Temperature
- OM5-IV-20A-C
 - Supply Voltage
- OM5-IV-1A-C
 - Supply Current (Voltage across 1 Ohm shunt)
- OMB-DBK207 - Analog Interface



Detector Interface I/O

- DCI5-C
 - Digital Input
- DCO5-C
 - Digital Output
- OMB-DBK208 - Digital Interface





Detector Interface Controller

- Provides Analog I/O, Digital I/O and Frequency I/O to Ethernet-Based Systems
- All I/O Can Be Synchronous, Enabling Precise Timing Between Various I/O Functions
- 8 Differential or 16 Single-Ended Inputs, Expandable up to 256 Voltage or 896 Thermocouple Channels Using Signal Conditioning and Expansion Options
- Up to 40 Built-In TTL-Level Digital I/O, Expandable Up to 256 Channels of Isolated I/O Using Low-Cost Isolation Modules
- Includes Support for Visual Basic, C/C++, ActiveX/COM, LabVIEW, MATLAB and DAS



OMB-DAQSCAN-2005



Gas Systems

- Systems were built, shipped and installed
- A few action items
 - Add repaired flow meters
 - Continue testing control software
 - Add sensors on hi pressure supply line
 - Perform pressure test by CERN/LHC compressed gases group
- All work must be done on site at CERN
 - Only some software studies at LBL



Detector Testing

- Since LHC beam returns in 2009 we plan to test the (spare) detector @ ALS BTS line
 - Validate new cable configuration on ALS beam
 - Test cable performance on high intensity signals
 - Infrastructure available from previous test
 - 2 axis table, gas lines, signal lines
 - Need to coordinate with analog electronics integration
 - Have only one spare

Detectors

- Modifications required to installed units
 - Add glass tubes
 - Add ceramic tubes
- Must follow assembly procedure almost from the beginning





DAQ System

- All hardware in the racks
 - Provided by CERN
- Firmware programming by LBNL
 - In two phases
- Software
 - Local LabVIEW by LBL
 - FESA class by CERN



DAQ System Testing

- Analog System-DAQ
 - Test full DAQ chain
 - From PA to shaper and DAB64
 - Including long cable



DAQ - Firmware Development

- Phase I - Completed
 - Counting mode
 - Threshold adjustments
 - Stacking
 - BOBR synch (bunch/orbit clock)



DAQ- Firmware Development

- Phase II
 - Pulse height discrimination
 - Deconvolution
 - Crossing angle support
- Will Complete in FY09
- Requires $L > 10^{32}$ for beam commissioning
 - 25 ns bunch spacing
 - Nominal bunch intensity
 - Collision multiplicity > 1
 - β squeeze



Software integration

- CERN will provide final software
 - System FESA class driver
 - Expert control panel
- No dedicated panel needed in the CCC
 - Only transfer lumi data through DIP at 1 Hz
- LabView software from LARP to operate the system
 - Will be replaced by final system when ready



Hardware commissioning

- Systems installation at CERN
 - Detector Controller Chassis
 - All rack equipment
 - Cabling checkup and calibration
- Detector installation
 - Electrical lab tests
 - Gas pressure lab tests
- Checkup lists



Detector Installation

- Modifications at IP1L and IP5R
 - Require to remove detectors from tunnel
 - Install ceramic sleeves and glass insulators
 - Repeat pressure, HV tests, RTD test
 - Re-install
- Removal/installation from TAN requires CERN transportation
- Removal from tunnel requires approval from CERN radioprotection



Detector High Voltage Testing

- Once mounted in pressure vessel
- Pressurize to 10 atm absolute
- Connect pre-amp
- Gradually ramp to 2.2kV
- Monitor each channel for leaks
 - Up to 10/min allowed
 - Test Pre-Amp alone first
- Procedure to be repeated after installation




Detector Production Checklist

- Pressure check
- Voltage test
- RTD test
- TDR measurements
- Labels
- QA documents



Detector installation checklist

- Ground connections
 - test single point in tunnel
- Preamp cabling checkout
- Gas pressure/flow test
- After PA connection
 - Test HV performance
 - Test PA with cal signals
 - Test relay selectors



Physics Studies

- MARS/Fluka modeling
 - In support of the ongoing systems development
 - In preparation for LHC beam operations
- SPS and other beam test data analysis
- DAQ programming support
 - Specification and testing



Project Support

- Project management
- Admin and budget support
- Travel
- Shipping

Summary

- Have defines all aspects of the project until its final completion
- WBS follows this outline
- This scope guides cost estimates and contingency analysis
- Beam Commissioning Support not included in project