



## US LHC Accelerator Research Program

*bnl - fnal- lbnl - slac*

# *Magnet Systems Status*

*P. Wanderer*

*LARP Magnet Systems Leader*

*DOE Annual Review*

*July 13, 2009*



## OUTLINE

Magnet names, length, aperture

Overview

Long quads (LQ)

Materials

Large-aperture model quads (HQ) [H = high]

Technology model quads (TQ)

FY10 draft budget


Five-year R&D plan

Response to previous review

Summary



# MAGNET NAMES, LENGTH, APERTURE





# MAGNET SEQUENCE TABLE

LARP magnet sequence table - V8b - July 2009

Type	Length [m]	Aperture [mm]	Gradient [T/m]	Peak coil Field [T]	Accelerator Qualities	Purpose	Comment
SQ	0.3	110 - 130	>80	>11	Alignment	Conductor, mechanical and quench studies	Complete
LR	4	0	N/A	>11	None	Length scale-up with racetrack coils	Complete
TQ	1	90	>200	>11	G, some FQ	Test bench	As needed
LQ	3.4	90	>200	>11	G, some FQ	Demonstrate Nb3Sn technology in long quads	2009 goal
HQ	1	120	>175	>14	G, FQ, alignment	Short model for QA, QB	High peak field
QA	2	120	> 175	> 14	G, FQ, alignment	Length effects, lifetime, alignment, etc.	make 4 (8)
QB	~ 6	120	> 175	> 14	All	Full-length demo coil(s)	\$ from APUL?



# OVERVIEW



## LARP MAGNET SYSTEM GOALS

- **Near term** (end of CY 2009): Nb<sub>3</sub>Sn quadrupole (LQ)
  - 200 T/m
  - 3.4 m
  - 90 mm  $\varnothing$  (aperture)
- **Medium term**: demonstrate the technology for use in LHC
- **Long term** (LHC Phase II upgrade, ~ 2020):
  - Nb<sub>3</sub>Sn IR quads



## AREAS OF WORK

- Underway for end of 2009: Long quadrupole, LQ:
  - Coils, support structures - make, assemble, test
- Results in hand:
  - **Magnetic mirror quad TQM** (conductor stability demonstration)
    - Funds from Fermilab off-project program
  - **Technology quads** (TQ - 1 m, 90 mm; TQS shell, TQC collar):
    - ~ 90%  $I_{ss}$  (200 T/m to 225 T/m)
    - Now: test bench for instability in quench current, axial preload,...
  - **Long racetrack** (LR - 3.6 m, racetrack coils):
    - ~ 96%  $I_{ss}$ , 11.5 T field on coil
    - shell structure development
- Underway:
  - HQ -  $\varnothing$  120 mm, 1 m,  $\cos 2\theta$
  - Materials: stability, properties during reaction
  - TQ - test bench (108/127 conductor, conductor with core)




# LONG QUADRUPOLES




# LQ SUPPORT STRUCTURES

## LQ #1 being assembled in shell structure



Collar



Shell



## LQ COIL STATUS

- Coil production methods developed (for now)
  - Fermilab winds, cures all coils;
  - Fermi & BNL react, impregnate
  - 1 m  $\rightarrow$  3.4 m coils **NOT** easy
- Five practice coils - each served multiple purposes
- Coils # 6 through #9 going into LQS01
  - That is, after five practice coils, the next four were ok (although not perfect - careful review before use in LQS01)



## LQ COIL AND REACTION FIXTURE



BNL/Fermilab review of coil-making procedures

Reaction fixture






## SUPPORT STRUCTURE STATUS

- **Shell development:**
  - 1 m shell structure with "dummy" coils (aluminum segments)
    - Assembled
    - Cooled to 77 K - forces measured - agreed with calculations
  - 3.4 m shell structure
    - Assembled 4 "1 m" lengths (no coils) at LBNL → alignment ok
    - Install 3.4 m dummy coils in support structure → ok
    - Cooled to 77 K at Fermilab - forces measured (72 strain gauges) - agreed with calculations
- **Collar: no work underway, no development needed**




## Assembly of full-length shell structure Sections 1 and 2 just before assembly





## Assembly of full-length structure 3.4 m long yoke-shell sub-assembly



July 13, 2009

2009 Annual DOE Review

14



Test of shell support structure with dummy coils at 77K at Fermilab




July 13, 2009

2009 Annual DOE Review

15



# LQ SCHEDULE





## LQ SCHEDULE HIGHLIGHTS UPDATE

- Reviews:
  - Support structure tests with dummy coils - April
  - Coils - June
  - Assembly plans - July
  - Test plan - ~ September
- LQS01 assembly begins later this month
- LQS01 test in October
- Options for LQ testing in FY10
  - test with all new 54/61 coils
  - replace one coil, retest (more likely option)





# MATERIALS

Available strands  
Inventory and orders  
Conductor R&D topics



## AVAILABLE STRANDS

- OST (Oxford Superconducting Technology) RRP<sup>®</sup> Nb<sub>3</sub>Sn:
  - 54/61 - LARP workhorse - used for racetrack, recent TQ, LQ
    - 54/61 with increased Cu/spacing  $\Rightarrow$  more strain tolerant
  - 108/127 - smaller filaments
    - Successful test in a "mirror" quad (see later slide)
    - Underway: "qualify" in a TQ (1m) - magnet test in July
    - More stable than 54/61 at same strand  $\varnothing$
    - In HQ (0.8 mm 108/127) same filament  $\varnothing$  as 0.7 mm 54/61 in TQ





## CONDUCTOR INVENTORY

- **LQ (54/61, 0.7 mm strand diameter, 70  $\mu\text{m}$  filament diameter)**
  - 26 kg = UL = unit length cable = 1 LQ coil
  - 12 UL's cable made (coils 4-15), **6 UL cable in inventory**
  - **Strand inventory is 78 kg (2-3 UL)**
- **HQ 54/61: (0.8 mm strand diameter, 80  $\mu\text{m}$  filament diameter)**
  - 54/61 (with increased Cu) (18 kg = UL = 1 HQ coil)
  - 5 UL's cable made, **3 UL cable in inventory**
- **HQ 108/127: (0.8 mm strand diameter, 57  $\mu\text{m}$  filament diameter)**
  - 108/127 (with increased Cu)
  - **Strand inventory is 117 kg (5 UL)**



## CONDUCTOR ORDERS

- Vendor: Oxford Superconducting Technology (NJ)
- 15 months from order to cable available for winding
- Some strand specifications can be changed ~ 6 months after order placed
  
- 88 kg order in process, due January 2010
  - Decide by September: 54/61 or 108/127?
- 70 kg order, place by end of July → delivery in April
  - 2 UL LQ or 3 UL HQ -- 54/61 or 108/127?
  
- Magnet Steering Committee to discuss later in July



## MATERIALS DEVELOPMENT UNDERWAY

- Conductor studies in strands, cables, magnets, as appropriate
  - Ongoing strand characterization (e.g., HQ cable development)
  - Underfunded by LARP → off-project support (FNAL, BNL)
- Conductor stability (see following slides)
  - Strands
  - Magnets (e.g., TQS02c, TQS03, and TQM [mirror])
- Strain tolerance
  - Strands (NIST)
  - Cables (initial test at NHMFL in May, at CERN this fall)
  - But only one campaign at each place is funded.
- Cable length at each stage of the reaction process




## MAGNET PERFORMANCE AT 1.9 K

- Critical issue -
  - TQS - 54/61 - quench current *decreased* as temperature lowered below 2.6 K
  - TQM - 108/127 ( $\Rightarrow$  smaller filaments than 54/61) - quench current increased as temperature lowered below 2.6 K.
  - TQS - 108/127 - test at CERN later this month
- Remark: HQ likely less sensitive to filament diameter than TQ/LQ, due to a lower load line ( $G$  vs.  $I$ )





# TQ502c training (20 A/s) vs. temperature [RRP 54/61, test at CERN]





## Mirror Design – Fermilab, off-project

TQC — TQM



The quadrupole mirror design TQM is based on the mechanical structure of the LARP technology quadrupole of TQC series. Three coils, stainless steel collar blocks and preload control spacers were replaced by the magnetic mirror blocks and spacers.



# Mirrors Quench Performance – Zlobin et al.

## 4.5 K:

Standard training behavior and typical ramp rate dependence.



## 1.9 K:

TQ coils made of **RRP-54/61** strand show  $I_q$  reduction and an erratic quench behavior during training and ramp rate studies.

unusual increase of the quench current at 200-275 A/s.

The new coil made of more stable **RRP-108/127** strand shows the expected  $I_q$  increase and regular ramp rate dependence.

This coil reached 98-99% of its SSL.





## MATERIALS R&D NOT FUNDED BY LARP

- Eddy current reduction - ESSENTIAL - UNDERWAY
  - Stainless steel ribbon ("core"), 25  $\mu\text{m}$  thick, inside cable
  - Increases resistance between top and bottom of cable  $\Rightarrow$  eddy current reduction
  - 1 coil made, test in magnetic mirror TQM (FNAL off project)
- Epoxy with increased radiation resistance
- Turn-to-turn insulation that can be wrapped around the cable
  - Replaces sleeve - needed for long cable lengths
- Measurement of magnet thermal margin (TQM02 off project)



## COIL #35 WITH CORED CABLE



Mirror Quadrupole  
Fermilab off-project  
Test this fall



# LARGE APERTURE QUAD (HQ)



## LARGE APERTURE (HQ) - 120 mm

- Reoptimization TQ  $\rightarrow$  HQ ( $\sim 1$  m):
  - Strand (0.7 mm  $\rightarrow$  0.8 mm), 54/61
  - Cable (10 mm  $\rightarrow$  15 mm, new keystone angle, heat treatment)
  - Coil (90 mm  $\rightarrow$  120 mm, new coil ends)
  - Support structure (max. o.d. for LHC, include alignment)




## HQ COIL STATUS

- Berkeley
  - Cable development (0.8 mm strand  $\varnothing$ )
  - First practice coil reacted; 2<sup>nd</sup> practice coil being wound
- BNL
  - Design reaction, impregnation fixtures
  - Scheduled to react, impregnate coils
- Fermilab
  - Design coil 2D, 3D cross section
  - Supply coil parts, ends & straight section



# FIRST HQ PRACTICE COIL



July 13, 2009

2009 Annual DOE Review


32



## HQS – Mechanical Shell based Structure

### Components

- Aluminum bolted collars => alignment
  - remains in compression from assembly to operating conditions
- Iron pads and yoke
- Iron master key => alignment
- axial rods => axial preload
- 25 mm aluminum shell => azimuthal preload
  - Coil and collar in compression
- Cooling area



570 mm outer diameter

### Assembly

- 60 mm bladders located outside the key span
- 38 MPa pressure (600 + 50 microns clearance for 220 T/m)
- Collars, pads and key locations optimize to minimize stress






# Short-sample limit in the straight section



1.9 K / 4.4 K	Layer 1			Layer 2		
<b>A/mm<sup>2</sup></b>	<b>2000</b>	<b>2500</b>	<b>3000</b>	<b>2000</b>	<b>2500</b>	<b>3000</b>
<b>I<sub>max</sub> (kA)</b>	<b>17.5/15.98</b>	<b>18.58/16.95</b>	<b>19.45/17.72</b>	18.14	19.30	20.22
<b>B<sub>max</sub> (T)</b>	<b>13.72/12.59</b>	<b>14.52/13.3</b>	<b>15.17/13.9</b>	13.55	14.34	14.98
<b>G<sub>max</sub> (T/m)</b>	<b>197/181</b>	<b>208/191</b>	<b>219/199</b>			



## HQ – Mechanical analysis Azimuthal stress in the coil



	Target 219 T/m
During bladder operation	-90 MPa
With loading key	-82 MPa
At 1.9 K	-177 MPa
With Lorentz forces	-177 / 20 MPa



=> High but acceptable stress at short sample

*Courtesy of H. Felice*



# HQ schedule – Rev. 7/02/2009

ID	TaskName	Start	Finish	Duration	Predecessors	Q3 '09			Q4 '09			Q1 '10			Q2 '10			Q3 '10			Q4 '10								
						Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct					
1	<b>Tooling, Parts, Practice Coils</b>	<b>Wed 4/15/09</b>	<b>Thu 8/20/09</b>	<b>90 days</b>																									
2	Practice winding/curing #1	Wed 4/15/09	Wed 6/10/09	40 days																									
3	Practice reaction/potting #1	Thu 6/11/09	Thu 7/9/09	20 days	2																								
4	Practice winding/curing #2	Thu 6/25/09	Thu 7/16/09	15 days	2FS+10 days																								
5	Practice reaction/potting #2	Fri 7/17/09	Thu 8/20/09	25 days	4																								
6	<b>Structure Design and Fabrication</b>	<b>Mon 2/2/09</b>	<b>Wed 11/18/09</b>	<b>205 days</b>																									
7	Structure Procurement	Mon 2/2/09	Tue 7/21/09	120 days																									
8	Structure pre-assembly	Wed 7/22/09	Wed 9/30/09	50 days	7																								
9	Mechanical model	Thu 10/1/09	Wed 11/18/09	35 days	8																								
10	<b>HQ01 Model</b>	<b>Fri 7/17/09</b>	<b>Wed 3/10/10</b>	<b>159 days</b>																									
11	Coil 3 Wind / Cure	Fri 7/17/09	Thu 8/6/09	15 days	4																								
12	Coil 4 Wind / Cure	Fri 8/7/09	Thu 8/27/09	15 days	11																								
13	Coil 5 Wind / Cure	Fri 8/28/09	Fri 9/18/09	15 days	12																								
14	Coil 6 Wind / Cure	Mon 9/21/09	Fri 10/9/09	15 days	13																								
15	Coil 3 React/Impreg	Fri 8/21/09	Fri 9/25/09	25 days	11,5																								
16	Coil 4 React/Impreg	Fri 8/28/09	Fri 10/2/09	25 days	12																								
17	Coil 5 React/Impreg	Mon 9/28/09	Fri 10/30/09	25 days	15,13																								
18	Coil 6 React/Impreg	Mon 10/12/09	Fri 11/13/09	25 days	14,16																								
19	Magnet Assembly	Thu 11/19/09	Tue 1/5/10	25 days	18,17,9																								
20	Test	Wed 1/6/10	Tue 2/9/10	25 days	19																								
21	Analysis & Reporting	Wed 2/10/10	Tue 3/9/10	20 days	20																								
22	Review	Wed 3/10/10	Wed 3/10/10	1 day	21																								
23	<b>HQ01b Model</b>	<b>Wed 12/2/09</b>	<b>Thu 7/1/10</b>	<b>144 days</b>																									
24	Coil 7 Wind / Cure	Wed 12/2/09	Tue 12/22/09	15 days	14FS+35 days																								
25	Coil 8 Wind / Cure	Wed 12/23/09	Thu 1/21/10	15 days	24																								
26	Coil 7 React/Impreg	Wed 12/23/09	Thu 2/4/10	25 days	24																								
27	Coil 8 React/Impreg	Fri 1/22/10	Thu 2/25/10	25 days	25																								
28	Magnet Assembly	Wed 3/24/10	Tue 4/27/10	25 days	27,20FS+30 days																								
29	Test	Wed 4/28/10	Wed 6/2/10	25 days	28																								
30	Analysis & Reporting	Thu 6/3/10	Wed 6/30/10	20 days	29																								
31	Review	Thu 7/1/10	Thu 7/1/10	1 day	30																								
32	<b>HQ02 Model</b>	<b>Thu 6/3/10</b>	<b>Thu 1/20/11</b>	<b>156 days</b>																									
33	Coil 9 Wind / Cure	Thu 6/3/10	Wed 6/23/10	15 days	29																								
34	Coil 10 Wind/cure	Thu 6/24/10	Thu 7/15/10	15 days	33																								
35	Coil 11 Wind / Cure	Fri 7/16/10	Thu 8/5/10	15 days	34																								
36	Coil 12 Wind / Cure	Fri 8/6/10	Thu 8/26/10	15 days	35																								
37	Coil 9 React/Impreg	Thu 6/24/10	Thu 7/29/10	25 days	33																								
38	Coil 10 React/Impreg	Fri 7/16/10	Thu 8/19/10	25 days	34																								
39	Coil 11 React/Impreg	Fri 8/6/10	Fri 9/10/10	25 days	35,37																								
40	Coil 12 React/Impreg	Fri 8/27/10	Fri 10/1/10	25 days	36,38																								



# FY10 DRAFT BUDGET



# LARP FY10 DRAFT MAGNET BUDGET

July 2, 2009 - V7												
P. Wanderer		Costs are in k\$										
Task	specifics	# items	\$/item	item total		BNL		FNAL		LBNL		
						labor	materials	labor	materials	labor	materials	
LQ	complete LQS01 test, analysis	1	\$168	\$168		0	0	56	6	106	0	
	LQS01b/02 assy, test, disassy	1	\$482	\$482		0	0	193	16	241	32	
	LQ coils #12 - #15	1	\$686	\$686		220	28	272	78	55	33	
	Reports, reviews	1	\$90	\$90		20	0	40	0	30	0	
			LQ total	\$1,426	<b>\$1,426</b>							
HQ	HQ01 build, test	1	\$685	\$685		15	0	124	23	457	66	
	HQ01b (see note), test	1	\$1,497	\$1,497		258	22	213	141	770	93	
			HQ total	\$2,182	<b>\$2,182</b>							
Materials	Cable/insulate UL LQ	2	\$28	\$55						41	14	
	Cable/insulate UL HQ	6	\$19	\$114						88	26	
	EDIA for LQ, HQ cable, insulate	1	\$74	\$74						74		
	Buy strand 10 UL QA	1	\$452	\$452		7		6	434	5		
	Strand tests (30 BNL, 25 Fermi)	1	\$313	\$313		144	22	127	20			
			Mat. Total	\$1,008	<b>\$1,008</b>							
QA	design only				<b>\$400</b>	\$400						
						total	1064	72	1031	718	1867	264
Total FY10 budget					<b>\$5,016</b>	lab total		1136		1749		2131



# FIVE-YEAR R&D PLAN



## TECHNOLOGY DEMONSTRATION PROGRAM

- **MAGNETS**

- Minimal set of magnets →

- 1 long (3.4 m), 90 mm aperture quad [LQ]

- 4 (6) medium-length (2 m), 120 mm aperture [QA]

- QA = 2 m version of HQ

- » Because HQ has only 30 cm of straight section

- **RELATED R&D**

- Carried out through core programs (i.e., off-project)




## FUNDING ASSUMPTIONS

- Guidance: LARP funding decreases \$1M/yr
- Assume: \$13 M LARP total for FY10
- Assume: Magnet fraction constant, ~ 38%, w/o contingency
  
- Develop QA budget, schedule using LQ experience
  - No built-in schedule contingency
  - Yield: assume build 5 coils, use 4 in a magnet
  - Two rebuilds included (replace 1 or 2 coils, retest)
  - Schedule requires parallel production lines, three labs
  - QA budget + LQ work + HQ (1 m, 120 mm) development (FY10, FY11) fits into budget (w/o contingency) for FY10-FY14.



# TIME FRAME - R&D, PRODUCTION





# RECOMMENDATIONS/ACTION ITEMS FROM JUNE 2008 REVIEW



## Action Items / Recommendations (1)

- 1. To ensure a reproducible manufacturing process, a single conductor and structure-type should be adopted to determine and quantify the effects of coil variability on magnet performance. This effort should be based on Oxford Type 54/61 conductor and the shelltype structure for testing LQ magnets.
  - *Response: LQS01 = shell; all LQ, HQ coils 54/61 as recommended*
- 2. At this juncture, restrict the use of more advanced conductors (such as Oxford Type 108/127) to tests involving short technology quadrupoles (TQ).
  - *Response: 108/127 only in TQS03, TQM03 (mirror), as recommended*



## Action Items / Recommendations (2)

- 3. Complete an accelerator-quality magnet design (HQ) as soon as possible, focusing on operational stability with a 2K temperature margin (with all loads).
  - *Response: As directed, HQ design, with some accelerator-quality features, completed; construction underway*
- 4. Should give priority to MCNPX-type of simulation of radiation effects over the work on decreasing the diameter of strands (Deff).
  - *As directed, no LARP funds for work on strands beyond 108/127. Test of magnet in beam discussed with CERN*



# SUMMARY



## CONCLUSIONS

- **Good progress toward demonstrating technology:**
  - 200 T/m achieved in 1 m model quads, both support structures
  - 96%  $I_{ss}$ , 11.5 T field achieved in 3.6 m racetracks
  - On track to test 3.4 m, 90 mm quad by end of CY 2009
  - Work on larger aperture well underway; test early CY 2010
  - 108/127 - increased stability
- **There is still a lot to do:**
  - Demonstrate 200 T/m in 3.4 m, 90 mm quad
  - Demonstrate full set of properties needed for accelerator use
    - As needed for demonstration, develop/understand/optimize superconducting & mechanical properties of  $Nb_3Sn$  materials and magnets



## ACKNOWLEDGEMENTS

- U.S. DoE High Energy Physics for consistent support of LARP and the Conductor Development Program
- Off-project support from magnet R&D programs at Fermilab, Berkeley, Brookhaven for timely assistance
- CERN for support of assemblies and tests of 1 m quads
- My LARP colleagues G. Ambrosio, M. Anerella, E. Barzi, R. Bossert, S. Caspi, G. Chlachidze, D. Dietderich, P. Ferracin, A. Goedeke, H. Felice, A. Ghosh, F. Nobrega, G. Sabbi, J. Schmalzle, and A. Zlobin.



backup



# TECHNOLOGY QUADS 1M QUADS - TQS, TQC

Now: test bench for new conductors, etc.




## TECHNOLOGY QUAD OVERVIEW

- Recall: length ~ 1 m, aperture 90 mm.
- With good RRP coils and proper assembly, exceed 220 T/m (4.5 K) and reach ~ 90%  $I_{ss}$   $\Rightarrow$  gradient goal reached
- Support structures now used for development tests
  - Stability/1.9 K performance versus number of filaments -
    - 54/61 (TQS02c) - results in hand
    - 108/127 (TQS03) - test at CERN July 09



# TQ SHELL SUPPORT STRUCTURE



aluminum shell



High axial preload