



# HQ Coil Fab at BNL

Jesse Schmalzle, BNL 11/04/09

J. Schmalzle

HQ Coil Fab at BNL - CM13 11/4/09

1




## HQ Coils



- Reaction and impregnation tools:
  - Similar to LQ tool with the addition of alignment pins.
  - Designed at BNL, fabricated at LBL.
- Coils wound and cured at LBL.
- HQ02 (practice coil) shipped to BNL in the impregnation tooling.
  - Shipping fixture not available.







J. Schmalzle




### HQ02 – prep for reaction



- Gaps at wedge ends.
- Gaps at endspacers.
- Turns lifted from mandrel.










J. Schmalzle



#### HQ02 - Reaction






HQ Coil Fab at BNL - CM13 11/4/09



#### HQ02 - Reaction









#### HQ02 – post reaction










#### HQ02 – post reaction



- Gaps at wedge ends .062"-.101"
- Gaps at endspacers.
- Turns lifted from mandrel.









J. Schmalzle




## HQ02 – prep for impreg



- Keyway filled
  - RTV, Solid fillers at pins.
- Holes packed with fiberglass.
- Nomex over saddle.
- Wires attached to circuit.









J. Schmalzle



### HQ02 – prep for impreg



- Fixture lift / rotate.
- Suspended from vacuum tank top plate.
- Mount strap heaters.












- Impregnation quality looks good.
- Final prep starting now ready to ship mid November.





#### HQ04 – prep for reaction



- Cured coil shipped using shipping fixture.
  - Oversize coil doesn't fit well fixture to be modified.
- Transferred to reaction tool using coil lift beam.
  - Shims required to accommodate oversize coil.









#### HQ04 – prep for reaction



- Cycle change now 48 hrs at 665 C (was 72 hrs).
- End spacer fit seems better, still have large wedge gaps .060"-.165".
- Reaction to start this week.
- Complete and ship mid January.

