

Magnet R&D plan

Iterated following advice from DOE
annual review committee

P. Wanderer

Nov. 4, 2009

LARP 13th Collaboration Meeting
Port Jefferson, NY

Two parts

- Iteration of R&D plan, following review
 - Magnet Steering Committee
- Preliminary schedule, budget for 6 m quads, additional HQ (1 m, 120 mm)
 - Mike Anerella, Jesse Schmalzle

Recommendation re: R&D plan

- Advance “technology demonstration” by 1 year, to 2013, to insure time for Nb₃Sn magnets produced for Phase II Upgrade, with installation in 2020.
- Response: Incorporate recommendations into R&D plan, keyed to future events (e.g., collaboration meetings)

Calendar

- DOE semi-annual review – January 2010
- CERN AP Workshop – January 2010
- CM14 – spring 2010
- DOE annual review – July 2010
- CM15 – fall 2010

Notes

- Review committee assumed 2 LQ (3.4 m, 90 mm), and 2 HQ (1 m, 120 mm) tested by end FY10.
- Note: Phase I Upgrade will have 120 mm quads (i.e., same as HQ)
 - 90 mm too small for Phase II Upgrade
- Recommend: use TQ (90 mm, 1 m) for technology studies not dependent on aperture (cheaper than 120 mm)

Point design, etc.

- CM13: Begin definition of point design for Phase II Quad → use it to prioritize the R&D list and estimate budget, resources, schedule for January 2010 DOE semiannual review
 - Begin with Mike Lamm's comprehensive list of magnet requirements

Issues settled/not settled

- Issues settled with 90 and 120 mm quads:
 - Quench, retraining, self protection, electrical integrity, preload (axial and azimuthal) vs. performance
- Issues not settled with LQ, HQ
 - Random harmonics → need longer HQ
 - Alignment → install in horizontal cryostat
 - Beam-heating / temp margin demonstration → CERN test beam

Need Phase II AP Input

- Optics priority: 2m, 120mm vs. 6m, ? aperture:
 - where does “random FQ” fit into R&D priority?
 - answer question at Chamonix workshop?
- Beam loss simulation, radiation:
 - Heat load, temperature margin, radiation damage -- with and w/o inner shield
- Cooling simulation: study both 4.5 K and 1.9 K
 - Cryo plant construction ok for Phase II.
 - Longitudinal cooling/Internal heat exchanger
- Stored energy/quench protection vs length/aperture/gradient

Input into point design

- CM14 (spring 2010): Refine point design using input from CERN/LHC Chamonix workshop and LHC experience w. beam
 - Begin conceptual design, have draft ready for review at fall workshop
- Peer review (= DOE annual review?)
 - Peer review *after* CM15 workshop?

CM15 (start of FY11)

- Workshop with CERN
 - Test data from LQ(3.4 m, 90 mm), HQ(1 m, 120 mm)
 - 1 year's LHC experience
 - Input from work started at Chamonix
 - Significant input from CERN magnet staff
- Workshop output: LARP + CERN agreement on Phase II quad parameters

CM15 (start of FY11)

- Begin two 6 m prototype quads to test in 2013
 - Use agreed upon Phase II specifications
 - Length may be adjusted for vertical testing
 - Finalize conceptual design, begin engineering design
 - Why 6 m?
 - Vertical dewar test of 6m possible at BNL
 - LARP or APUL II?
 - Directed by one institution?

Support from core programs

- Berkeley:
 - Cable testing at NHMFL
 - End making 90 mm coils (focus on 120 mm)
- Fermilab:
 - TQM (90 mm, 1 m, magnetic mirror) as R&D vehicle (e.g., cable with core)
 - No core support after FY10
- Brookhaven:
 - Strand and cable testing
- CERN:
 - Tests in beam

Notes from magnet committee to DOE

- Nb₃Sn magnets are LARP's highest priority
- May need extra funding to complete work by 2013
 - No contingency in plans presented in July

US LHC Accelerator Research Program

bnl - fnal- lbnl - slac

*LARP 5 Year R&D Plan
Proposal*

November 4, 2009

Plan Scope / Goals

- Work starts in FY11
- Assumes: 2LQ, 2HQ complete in FY10
- Two (Four?) 1m HQ Cold Masses
 - Accelerator requirements per M. Lamm outline
- Two (Four?) 1m HQ “Rebuilt” (i.e. 1 or 2 new coils) Cold Masses
 - Iterate, refine as presented by previous results
- Suspend LQ work after FY10 to focus resources on HQ, QA
- One (1) 6m mirror coil test
- Two 6m QA Cold Masses
 - → Complete in FY13 to support 2020 production deliveries at CERN (actual schedule projection completion in US is Jan 2019)


FY10

1. order strand for 12 1m UL's (14 UL's if possible)
 - Related Activities:
 - Ongoing LQ, HQ work – “preview” QA features as possible/prudent (HQ continues into FY11, FY12?)


FY11-FY13: (1) mirror assembly, (2) 6m cold masses
(mirror test in FY12, cold mass tests in FY13)

- Assume 6 coils for every magnet:
 - FNAL and BNL each wind/cure/react/pot 3 coils per cold mass
 - FNAL ships coils to BNL for assembly and test
 - LBNL designs/builds/ships support fixture to BNL
- New requirements for 6m:
 - Winding/curing tooling (F&B)
 - Curing press extension (B)
 - Reaction Oven extension (B)
 - Mirror coil support (F)
 - Support structure (L)
 - Vertical dewar mods (B)
- Note: times are based on experience with LQ, increased slightly. Material, tooling costs are scaled from HQ CM13

Schedule p.1



Schedule p.2



Magnet Test Dates

- HQ # 3,4
 - October 2011
 - March 2012
- 6 m Quads
 - Mirror July 2012
 - May 2013
 - September 2013

Costs

- Preliminary cost: \$18.1 M
 - Does not include essential ancillary R&D
- If costs are prohibitive:
- Delete BNL winding/ curing tooling, press extension, reaction oven extension; wind/cure/react/pot all coils at FNAL (takes longer) – saves \$1.1 M
- Delete FNAL mirror coil assembly to save time (also saves additional costs) – saves \$0.65 M

For comparison

- Cost of “2010-2014” R&D (July plan – 4 2m, 120 mm + rebuilds, no 6 m) in 4 years, not 5. Cost: guess ~ same total as before, \$21.1M (FY10 through FY14)