



US LHC Accelerator Research Program

bnl - fnal- lbnl - slac

Status of Magnet R&D

P. Wanderer, BNL

LARP Magnet Systems Leader

CERN-US annual meeting

January 13, 2009

Geneva



OUTLINE

Overview

Long quads (LQ)

Large-aperture model quads (HQ)

Materials

Technology model quads (TQ)

A look ahead

Summary



OVERVIEW



LARP MAGNET SYSTEM GOALS

- **Near term (end of CY 2009):** Nb₃Sn quadrupole (LQ)
 - 200 T/m
 - 3.6 m
 - 90 mm \varnothing (aperture)
- **Long term (LHC Phase II upgrade, ~ 2015):**
 - Nb₃Sn IR quads



AREAS OF WORK

- Underway for end of 2009: Long quadrupole, LQ:
 - Coils, support structures - make, assemble, test
- Results in hand:
 - Technology quads (TQ - 1 m, 90 mm; TQS shell, TQC collar):
 - ~ 90% I_{ss} (200 T/m to 225 T/m)
 - Test bench for instability in quench current, axial preload
 - Long racetrack (LR - 3.6 m, racetrack coils):
 - ~ 96% I_{ss} , 11.5 T field on coil
 - shell structure development
- Underway:
 - HQ - \varnothing 120 mm, 1 m, $\cos 2\theta$
 - Materials: stability, properties during reaction
 - TQ - test bench (new conductor)



LARP Magnet Sequence Table

LARP magnet sequence table - V7b - January 2009


Type	Length [m]	Aperture [mm]	Gradient [T/m]	Peak coil Field [T]	Accelerator Qualities	Purpose	Comment
SQ	0.3	110 - 130	>80	>11	Alignment	Conductor, mechanical and quench studies	Complete
LR	4	0	N/A	>11	None	Length scale-up with racetrack coils	Complete
TQ	1	90	>200	>11	Mag. measurements	Test bed for conductor & LQ	Ongoing
LQ	4	90	>200	>11	Support structure	Demonstrate Nb ₃ Sn technology in long quads	2009 goal
HQ	1	120	>175	>14	Field Q & alignment	Short model for QA	High peak field
QA	~ 4	120	120	~ 10	All	Length effects, lifetime, alignment, etc.	
QB	tbd	tbd	tbd	tbd	All	Phase 2 upgrade magnet	




LONG QUADRUPOLES



LQ COIL, SUPPORT STRUCTURES



Collar



Shell



LQ COIL STATUS

Development of coil production methods complete (for now)

One nasty problem overcome - loading of Ti poles after reaction

-- essential info from expert at CERN

Numerous other issues

1 m → 3.8 m coils not easy

Production of the first 4 coils for LQS01 underway

[Fermilab winds, cures all coils; both labs react, impreg.]

Fermilab: #6 - ready for impregnation; #8 - wound, cured

BNL: #7 - reaction complete; #9 - ship cured coil to BNL soon

Schedule: Coil #9 (4TH for LQS01) shipped to Berkeley in April



LQ COIL AND REACTION FIXTURE



Reacted coil - lead prep

Reaction fixture






SUPPORT STRUCTURE STATUS

- **Collar: components purchased (no development needed)**
- **Shell development:**
 - 1 m shell structure with "dummy" coils (aluminum segments)
 - Assembled
 - Cooled to 77 K - forces measured - agreed with calculations
 - 3.8 m shell structure
 - Assembled 4 "1 m" lengths (no coils) → alignment ok
 - Install 3.8 m dummy coils in support structure → ok
 - Next: 77 K cooldown at Fermilab, attached to warm-cold interface and support -- February



Assembly of full-length structure Section 1 and 2 before joining operation





3.2 m long coil-pack sub-assembly





LQS trial assembly #1, dummy coils, room temp.

- Successful trial assembly – all goals achieved:
 - Strain gauges on dummy coils, shell, axial support rods
 - No major problems
 - Axial preload works to at least 10% > design
 - Azimuthal preloads of shell, dummy coil consistent
 - Azim. preload will be increased to reach design goal by adding 75 μm shims to keys during next trial assembly



LQ SCHEDULE HIGHLIGHTS

- LQS01 assembly begins in May
 - Handling of 3.8 m practice coils begins earlier
- LQS01 test in September
- Options for LQ testing in FY10
 - shell support with all new coils
 - replace one coil, retest in shell structure
 - collar support structure (LQC)



LARGE APERTURE QUAD (HQ)



HQ DESIGN STUDY: 134 mm → 110 mm → 120 mm

- **Reoptimization TQ → HQ:**
 - Strand (0.7 mm → 0.8 mm), 54/61
 - Cable (10 mm → 15 mm, keystone, heat treatment)
 - Coil (90 mm → 120 mm, new coil ends)
 - Support structure (max. o.d. for LHC, include alignment)
- **Testing planned for end of CY09.**



HQ STATUS


- BNL
 - Drawings for reaction, impregnation fixtures submitted to BNL shops
- Fermilab
 - Coil design completed
 - Drawings for coil end parts released for quotes
- Berkeley
 - Cable development completed (0.8 mm strand \emptyset)
 - Most of the tooling for coil winding and curing is in-house, now being assembled



HQS – Mechanical Shell based Structure

Components

- Aluminum bolted collars => alignment
 - remains in compression from assembly to operating conditions
- Iron pads and yoke
- Iron master key => alignment
- axial rods => axial preload
- 25 mm aluminum shell => azimuthal preload
 - Coil and collar in compression
- Cooling area




570 mm outer diameter

Assembly

- 60 mm bladders located outside the key span
- 38 MPa pressure (600 + 50 microns clearance for 220 T/m)
- Collars, pads and key locations optimize to minimize stress



3D analysis - Tosca







Short-sample limit in the straight section

1.9 K / 4.4 K	Layer 1			Layer 2		
A/mm²	2000	2500	3000	2000	2500	3000
I_{max} (kA)	17.5/15.98	18.58/16.95	19.45/17.72	18.14	19.30	20.22
B_{max} (T)	13.72/12.59	14.52/13.3	15.17/13.9	13.55	14.34	14.98
G_{max} (T/m)	197/181	208/191	219/199			




Critical temperature T_c (120 T/m) = 10.7 K



HQ – Mechanical analysis Azimuthal stress in the coil



	Target 219 T/m
During bladder operation	-90 MPa
With loading key	-82 MPa
At 1.9 K	-177 MPa
With Lorentz forces	-177 / 20 MPa



=> High but acceptable stress at short sample

Courtesy of H. Felice



MATERIALS

Available strands

Magnet instability at low temp.



Other work

[Conductor pipeline - ok]



AVAILABLE STRANDS

- OST RRP® Nb₃Sn:
 - 54/61 - LARP workhorse - used for LR, recent TQ, LQ
 - 108/127 - recently became a standard product
 - Underway: "qualify" in a TQ (1m) - coils now being made
 - More stable (see below) than 54/61 at same strand \varnothing
 - In HQ (0.8 mm 108/127) same filament \varnothing as 0.7 mm 54/61 in TQ





CONDUCTOR/MAGNET INSTABILITY

TQ QUENCH PERFORMANCE LOWER, ERRATIC AT 1.9 K

Source of instability:

conductor only?

conductor + magnet construction (i.e., conductor damage)?

Temperature threshold ~ 2.5 K

I_q decreases (13 kA \rightarrow 11.6 kA) at ~ 2.5 K

STRAND TESTS

Instability at medium field (6 T)

"self field" instability differentiated from low field "flux jump" instability (which we know how to avoid)


Instability onset between 2K and 2.5 K (Lambda point 2.17 K)

AN ACTIVE AREA OF STUDY ...

[Note: HQ load line $<$ TQ load line \Rightarrow instabilities in HQ $<$ TQ]




TQS02c training (20 A/s) vs. temperature [RRP 54/61, test at CERN]






RRP 108/127 0.7 mm 640C/48h RRR~ 310 (high)





RRP 108/127 vs. 54/61 RRR~ 310 (both 0.7 mm)





OTHER MATERIALS WORK


- **Cable R&D Underway:**
 - Measure cable length change at each stage of reaction
 - Measure cable J_c versus stress transverse to plane of cable
 - NHMFL in Florida (Jan.) - vary preload while cold, 4.2 K
 - CERN FRESCA (summer 09), 4.2 K and 1.9 K [also: stability]
- Strand degradation (rolling) vs. cable degradation
- "Self-field" instability model (Bordini, Rossi) fits some strand measurements
- **Needed, not yet funded:**
 - Manufacture "cored" cable (25 μm stainless steel strip inside cable, to increase interstrand resistance R_I), test in TQ for reduced ramp rate effects on gradient, harmonics
 - Measure thermal margin in cable, magnet



TECHNOLOGY QUADS 1M QUADS - TQS, TQC



TQ/LQ COLLAR SUPPORT STRUCTURE




"No" axial
preload - i.e.,
"no gap"

Stainless
steel shell



TQ SHELL SUPPORT STRUCTURE



aluminum shell



High axial preload



CONCLUSIONS FROM TQ CONSTRUCTION & TESTING

- Thorough review of TQ data by videoconference (Sept., Oct.)
 - Talks by Bossert, Caspi, Chlachidze, Felice, Ferracin
- Firm Conclusions:
 - With good RRP coils and proper assembly, exceed 200 T/m (4.5 K) and reach $\sim 90\% I_{ss}$
 - Same coils used in both structures reached \sim same fraction I_{ss} (caveat: TQC02e testing limited by leads)
 - 1.9 K (superfluid):
 - MJR performs as expected (i.e., I_q increases)
 - RRP erratic, I_q generally lower than at 4.5 K
 - Some of the causes that limit magnet quench performance



MORE TQ CONCLUSIONS

- Conclusions:
 - Poles must be bonded to coils
 - Etc. (other "minor" construction features)
 - Some of the causes that limit magnet performance
- Not yet settled:
 - Source of 1.9 K RRP erratic quench performance
 - Either end preload (high or "snug") ok
 - TQS02d reached 97% of previous quench plateau with end support reduced to ~ 76% of that of the previous assembly



A LOOK AHEAD



NEEDED TO DEMONSTRATE "ACCELERATOR QUALITY"

- **Model HQ magnets (~ 1 m) to study/demonstrate:**
 - Quench performance, margin w. r. to operating field
 - Field quality (mean, rms, uncertainty in mean, cross section iteration - 2D and ends, alignment) - 6 magnets for initial cross section, 6 magnets for final (iterated) cross section.
 - Lifetime (multiple thermal cycles, at least two magnets)
 - Additional coil production tooling
 - Additional support structure(s), test facility
- **QA (long version of HQ)**
 - Field quality as above (6 magnets)
 - Lifetime as above (operation in cryostat)
 - "Medium" level of instrumentation
 - Additional coil production tooling, support structure
 - Operation in test beam at CERN



PLANNING

- Have info on staff, calendar time, materials to make TQ, LQ, HQ (some)
- Iterate initial list of magnets, goals with LARP Magnet Steering Committee, CERN
- Draft plan available in March, presented at CM12 in April. Five-year plan presented at DOE Annual Review in June.
- Remark: At some point, funding would shift from LARP to APUL (Accelerator Project for the Upgrade of the LHC).
- To keep in mind: When will CERN decide that CERN will need to build magnets for the Phase 2 upgrade?



SUMMARY



CONCLUSIONS

- **Good progress toward establishing technology:**
 - 200 T/m achieved in 1 m model quads, both support structures
 - 96% I_{ss} , 11.5 T field achieved in 3.6 m racetracks
 - On track to test 3.6 m quad by end of CY 2009
 - Work on larger aperture well underway; test end CY 2009
- **There is still a lot to do:**
 - Demonstrate 200 T/m in 3.6 m, 90 mm quad
 - Develop/understand/optimize superconducting & mechanical properties of Nb_3Sn materials and magnets
 - Demonstrate full set of properties needed for accelerator use
 - Establish engineering phase space (aperture, gradient, etc.)



ACKNOWLEDGEMENTS

- U.S. DoE High Energy Physics for consistent support of LARP and the Conductor Development Program
- "Core" magnet R&D programs at Fermilab, Berkeley, Brookhaven for timely assistance
- CERN for support of assemblies and tests of 1 m quads
- My LARP colleagues G. Ambrosio, M. Anerella, E. Barzi, R. Bossert, S. Caspi, D. Dietderich, P. Ferracin, H. Felice, A. Ghosh, F. Nobrega, G. Sabbi, J. Schmalzle, and A. Zlobin.